

AD-A105 793


NEW YORK STATE DEPT OF ENVIRONMENTAL CONSERVATION ALBANY F/G 13/13
NATIONAL DAM SAFETY PROGRAM. STUMP POND DAM (INVENTORY NUMBER N--ETC(U)
MAR 81 G KOCH

DACWS1-79-C-0001

NL

UNCLASSIFIED

1 1 1
A
A 105 793



END
DATE
FILMED
81
DTIC

LEVEL II

5

AD A105793

DTIC
ELECTE
S OCT 20 1981 D
D

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD-A40 5793	
4. TITLE (and Subtitle) Phase I Inspection Report Stump Pond Dam. Susquehanna River Basin, Cortland County, N.Y. Inventory No. 746		5. TYPE OF REPORT & PERIOD COVERED Phase I Inspection Report National Dam Safety Program
7. AUTHOR(s) 10 GEORGE KOCH		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS New York State Department of Environmental Conservation 50 Wolf Road Albany, New York 12233 393970		8. CONTRACT OR GRANT NUMBER(s) 13 DACW51-79-C-1111
11. CONTROLLING OFFICE NAME AND ADDRESS Department of the Army 26 Federal Plaza New York District, CofE New York, New York 10287		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 12 67
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Department of the Army 26 Federal Plaza New York District, CofE New York, NY 10287		12. REPORT DATE 11 23 Mar 1981
		13. NUMBER OF PAGES
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; Distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) 6 National Dam Safety Program, Stump Pond Dam (Inventory Number 746), Susquehanna River Basin, Cortland County, New York. Phase I Inspection Report.		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety National Dam Safety Program Visual Inspection Hydrology, Structural Stability Stump Pond Dam Cortland County Susquehanna River Basin		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization. Visual inspection of this dam and engineering analyses revealed that the poor condition of the dam creates a hazard to human life and property. As a result of these determinations, the dam has been assessed as "unsafe, non-emergency."		

One of the spillway sections has failed completely, creating a large void in the dam. The other spillway channel is in poor condition, having cracks in the concrete and several small voids. The earth fill upstream of the dam completely blocks the failed spillway section and partially blocks the other section.

Using the Corps of Engineers' Screening Criteria for initial review of the spillway adequacy, it has been determined that the structure would be overtopped for all storms exceeding 10% of the Probable Maximum Flood (PMF). Due to the condition of the structure, it is questionable as to whether it could withstand a substantial flow over the crest. Another large void on the left end of the dam would be a likely problem area if overtopping were to occur. Since failure of the dam would increase the hazard from that which would exist just prior to the failure, the spillway is adjudged to be seriously inadequate.

Due to the serious nature of the deficiencies, it is recommended that within 30 days of the notification to the owner that the dam has been assessed as unsafe, repair work on the structural deficiencies should be commenced. These repairs should be completed within 3 months.

Within 3 months of the notification of the owner, a detailed hydrologic/hydraulic investigation should be commenced. This investigation should accurately define the site specific characteristics of the watershed and determine appropriate mitigating measures to be taken in response to the seriously inadequate spillway capacity. These measures should be completed within 1 year of the date of notification.

Other deficiencies noted should also be corrected within 1 year. Among these deficiencies are erosion along the downstream slopes of the right abutment, trees growing at the downstream toe, cracked concrete on the abutments at the ends of the spillway, no reservoir drain, and the lack of an emergency action plan.

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Avail and/or	
Dist	Special
A	

RECEIVED
JUN 20 1981
D

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
STUMP POND DAM
I.D. No. NY 746
CORTLAND COUNTY, NEW YORK

TABLE OF CONTENTS

	<u>PAGE NO.</u>
- ASSESSMENT	-
- OVERVIEW PHOTOGRAPH	-
1 PROJECT INFORMATION	1
1.1 GENERAL	1
1.2 DESCRIPTION OF PROJECT	1
1.3 PERTINENT DATA	2
2 ENGINEERING DATA	3
2.1 GEOTECHNICAL DATA	3
2.2 DESIGN RECORDS	3
2.3 CONSTRUCTION RECORDS	3
2.4 OPERATION RECORD	3
2.5 EVALUATION OF DATA	3
3 VISUAL INSPECTION	4
3.1 FINDINGS	4
3.2 EVALUATION OF OBSERVATIONS	4
4 OPERATION AND MAINTENANCE PROCEDURES	6
4.1 PROCEDURE	6
4.2 MAINTENANCE OF DAM	6
4.3 WARNING SYSTEM IN EFFECT	6
4.4 EVALUATION	6

	<u>PAGE NO.</u>
5 HYDROLOGIC/HYDRAULIC	7
5.1 DRAINAGE AREA CHARACTERISTICS	7
5.2 ANALYSIS CRITERIA	7
5.3 SPILLWAY CAPACITY	7
5.4 RESERVOIR CAPACITY	7
5.5 FLOODS OF RECORD	7
5.6 OVERTOPPING POTENTIAL	7
5.7 EVALUATION	8
6 STRUCTURAL STABILITY	9
6.1 EVALUATION OF STRUCTURAL STABILITY	9
7 ASSESSMENT/RECOMMENDATIONS	10
7.1 ASSESSMENT	10
7.2 RECOMMENDED MEASURES	10

APPENDIX

- A. PHOTOGRAPHS
- B. VISUAL INSPECTION CHECKLIST
- C. HYDROLOGIC/HYDRAULIC ENGINEERING DATA AND COMPUTATIONS
- D. REFERENCES
- E. DRAWINGS

Phase I Inspection Report
National Dam Safety Program

Name of Dam:	Stump Pond Dam I.D. No. NY 746
State Located:	New York
County Located:	Cortland
Watershed:	Susquehanna River Basin
Date of Inspection:	October 23, 1980

ASSESSMENT

Visual inspection of this dam and engineering analyses revealed that the poor condition of the dam creates a hazard to human life and property. As a result of these determinations, the dam has been assessed as "unsafe, non-emergency."

One of the spillway sections has failed completely, creating a large void in the dam. The other spillway channel is in poor condition, having cracks in the concrete and several small voids. The earth fill upstream of the dam completely blocks the failed spillway section and partially blocks the other section.

Using the Corps of Engineers' Screening Criteria for initial review of the spillway adequacy, it has been determined that the structure would be overtopped for all storms exceeding 10% of the Probable Maximum Flood (PMF). Due to the condition of the structure, it is questionable as to whether it could withstand a substantial flow over the crest. Another large void on the left end of the dam would be a likely problem area if overtopping were to occur. Since failure of the dam would increase the hazard from that which would exist just prior to the failure, the spillway is adjudged to be seriously inadequate.

> Due to the serious nature of the deficiencies, it is recommended that within 30 days of the notification to the owner that the dam has been assessed as unsafe, repair work on the structural deficiencies should be commenced. These repairs should be completed within 3 months.

Within 3 months of the notification of the owner, a detailed hydrologic/hydraulic investigation should be commenced. This investigation should accurately define the site specific characteristics of the watershed and determine appropriate mitigating measures to be taken in response to the seriously inadequate spillway capacity. These measures should be completed within 1 year of the date of notification.

Other deficiencies noted should also be corrected within 1 year. Among these deficiencies are erosion along the downstream slopes of the right abutment, trees growing at the downstream toe, cracked concrete on the abutments at the ends of the spillways, no reservoir drain, and the lack of an emergency action plan.

George Koch

George Koch
Chief, Dam Safety Section
New York State Department
of Environmental Conservation
NY License No. 45937

Approved By:

W. M. Smith Jr.
Colonel W. M. Smith Jr.
New York District Engineer

Date:

29 MAR 1971



OVERVIEW
STUMP POND DAM
I.D. No. NY-746

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
STUMP POND DAM I.D. NO. NY 746
DEC #95A-4270 SUSQUEHANNA RIVER BASIN
CORTLAND COUNTY, NEW YORK

SECTION 1: PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase I inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the National Dam Inspection Act, Public Law 92-367.

b. Purpose of Inspection

This inspection was conducted to evaluate the existing conditions of the dam, to identify deficiencies and hazardous conditions, to determine if these deficiencies constitute hazards to life and property, and to recommend remedial measures where required.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam

The Stump Pond Dam is a laid up stone structure with an earth fill upstream of the main dam.

The dam is approximately 100 feet long and a maximum of 15 feet high. The stone dam is exposed on the downstream face. The dam consists of two spillway sections each about 15 feet wide. These spillway sections are in the center of the structure. At either end there is a laid up stone segment which ties into natural ground. The laid up stone is founded on a concrete footing of unknown thickness. The earth fill segment, upstream of the main dam, was apparently added sometime after the initial construction of the dam.

The spillway has two adjoining sections each approximately 15 feet wide. A 2.5 foot wide concrete corewall on the upstream face forms the spillway crest. The earth fill has partially blocked the left channel and completely blocked the right channel.

b. Location

This dam is located in the Town of Willet, off New York State 41, approximately 1½ miles southeast of the Village of Willet. The dam is situated on Willet Creek.

c. Size Classification

The dam is 15 feet high and has a maximum storage capacity of 200 acre-feet. Therefore, the dam is in the small size capacity as defined by the "Recommended Guidelines for Safety Inspection of Dams."

d. Hazard Classifications

This dam is classified as "high" hazard due to the presence of several homes and trailers located downstream of the dam in the hamlet of Georgetown.

e. Ownership

The dam is owned by Mr. William Sudbrink, P.O. Box 42, Willet, New York 13863.

f. Purpose of Dam

The dam is used to maintain the water surface of Stump Pond for recreational purposes.

g. Design and Construction History

No information was available concerning the design or construction of this dam.

h. Normal Operating Procedures

There are no prescribed operating procedures for this structure.

1.3 PERTINENT DATA

a. Drainage Area (acres)

870

b. Discharge at Dam (cfs)

Open Spillway Channel (W. S. at top of dam)

135

c. Elevation (USGS Datum)

Top of Dam

1265

Spillway Crest

1262

d. Reservoir-Surface Area (acres)

Top of Dam

59

Spillway Crest

39

e. Storage Capacity (acre-feet)

Top of Dam

260

Spillway Crest

200

f. Dam

Type: Laid up stone with earth fill on upstream side

Dam Length (ft.)

100

Crest Width (ft.)

8.5

g. Spillway

Type: Uncontrolled rectangular concrete weir. Crest formed by 2.5 foot wide concrete core wall on upstream face.

Length: (ft.): Left Channel

15.2

Right Channel (blocked)

15

h. Reservoir Drain - None

SECTION 2: ENGINEERING DATA

2.1 GEOTECHNICAL DATA

a. Geology

The Stump Pond Dam is located in the Glaciated Allegheny Plateau physiographic province of New York State. This plateau is underlain by a great thickness of sedimentary rocks from the Devonian Era which lie almost horizontal. Severe trenching by streams and glacial erosion has carved the upland into a rugged terrain. The Susquehanna Hills rise to elevations of 1,700 to 2,000 feet between the rolling, relatively narrow valleys. The surficial soils and features of the area are the result of glaciations during the Cenozoic Era, the last of which was the Wisconsin glaciation.

A review of the "Brittle Structures Map of the State of New York" indicated that there are no faults in the immediate vicinity of the dam.

2.2 DESIGN RECORDS

No records were available concerning the design of this structure.

2.3 CONSTRUCTION RECORDS

No construction records were available.

2.4 OPERATION RECORDS

No operation records were available.

2.5 EVALUATION OF DATA

Data available for the preparation of this report was very limited. Most of the information used was based on measurements made at the time of the inspection. The Phase I inspection report was prepared using the limited data plus certain qualifying assumptions.

SECTION 3: VISUAL INSPECTION

3.1 FINDINGS

a. General

Visual inspection of the Stump Pond Dam was conducted on October 23, 1980. The weather was clear and sunny with the temperature in the forties. The water surface at the time of the inspection was 4 inches above the spillway crest. Water was flowing over the spillway and debris was blocking the entrance to the channel at the upstream face of the dam.

b. Dam

A number of serious deficiencies were noted on this structure. Among these deficiencies were the following:

1. The right spillway section had failed completely. The concrete and stones which originally formed the crest were no longer in place and a large void extended across the 15 foot width of the channel (see photo 1). Stones had been removed down to about 3 feet below the original spillway crest. The void extended from the downstream face to approximately 3 feet into the structure (see photo 2).
2. The left spillway section was in poor condition. The concrete on the crest was cracked and deteriorated. The concrete slab on the upstream apron was separated from the concrete on the crest (see photo 3). At the time of the inspection, the water was flowing into this crack and down through the laid up stone rather than over the spillway. There were two small voids in this section, each approximately 1 foot deep. One void was near the center of the section and the other at the right end. The pier which separates the two spillway channels was undermined and cracked (see photo 4).
3. The earth fill which had been placed upstream of the laid up stone section completely blocked the right spillway channel and partially blocked the other (see photo 5). The opening in front of the right channel was about 10 feet wide and 2 feet deep. The spillway capacity of this structure was limited by this opening.
4. There was another large void in the laid up stone on the left end of the dam. This void was about 6 feet wide by 5 feet deep (see photo 6). At the crest, the width of the stone remaining in this area was about 18 inches.
5. A bulge was noted in the laid up stone segment below the spillway section (see photo 7).
6. The stones at the right end of the dam were displaced upward above the horizontal with respect to the remainder of the dam (see photo 8).
7. The right abutment slope on the downstream face of the dam was very steep. There was a potential for surface runoff to cause erosion

problems in this area, further jeopardizing the stability of the dam. There were a number of trees and tree stumps along the downstream toe of the dam. Roots from these trees extended into the dam, creating additional stability problems.

9. There was apparently no reservoir drain. A 1 foot square opening was noted at the downstream toe, but this only extended a few feet into the dam.
10. The concrete abutment at the left end of the left spillway was cracked and deteriorated (see photo 10). There were both horizontal and vertical cracks on this abutment.

c. Downstream Channel

The channel immediately downstream of the dam was narrow and tree lined.

d. Reservoir

There was no indication of soil instability in the reservoir area. There appears to have been substantial sedimentation in the vicinity of the dam.

3.2 EVALUATION OF OBSERVATIONS

The overall condition of this dam is poor. A number of deficiencies exist which pose a threat to the stability of the structure. The following items were the most serious deficiencies noted:

- a. Large voids on the right spillway section and on the left end of the dam.
- b. Overall deterioration of the left spillway section, including cracked concrete and voids in the channel.
- c. The earth fill severely limits spillway capacity.
- d. A bulge in the laid up stone segment.
- e. Trees and tree stumps along the downstream toe of the dam.
- f. Deteriorated and cracked concrete on the left abutment of the left spillway.

SECTION 4: OPERATION AND MAINTENANCE PROCEDURES

4.1 PROCEDURES

There are no operating procedures for this dam.

4.2 MAINTENANCE OF DAM

No regular maintenance is performed on this structure.

4.3 WARNING SYSTEM IN EFFECT

No apparent warning system for evacuation of downstream residents is present.

4.4 EVALUATION

The operation and maintenance procedures on this dam are unsatisfactory. The overall poor condition of the dam is evidence of the deficiency in the maintenance procedures.

SECTION 5: HYDRAULIC/HYDROLOGIC

5.1 DRAINAGE AREA CHARACTERISTICS

Delineation of the watershed draining into the reservoir pool area was made using the USGS 7½ minute quadrangle sheets for Willet and Smithville Flats, New York. The 870 acre drainage area consists of open fields and wooded lands. Relief in the drainage area is moderate to steep with slopes ranging from 8 to 31 percent.

5.2 ANALYSIS CRITERIA

The analysis of the floodwater retarding capability of this dam was performed using the Corps of Engineers HEC-1 computer program, Dam Safety version. This program develops an inflow hydrograph using the "Snyder Synthetic Unit Hydrograph" method and then uses the "Modified Puls" flood routing procedure. The spillway design flood selected was the PMF in accordance with the Recommended Guidelines of the U.S. Army Corps of Engineers.

5.3 SPILLWAY CAPACITY

The dam has two ungated spillway channels. One of the spillway channels has been completely blocked by the earth fill which has been placed on the upstream face of the dam. The earth fill blocks a portion of the left spillway channel as well. The result is that the spillway capacity is controlled by the 10 foot wide channel through the earth fill. The spillway was analyzed as a broad crested weir with a discharge coefficient (c) of 2.6.

5.4 RESERVOIR CAPACITY

Normal storage capacity of the reservoir with the water surface at the spillway crest is 200 acre feet. Surge storage capacity between the spillway crest and the top of the dam is 60 acre feet, which is equivalent to a runoff depth of 0.83 inches over the drainage area.

5.5 FLOODS OF RECORD

No information was available regarding the occurrence of the maximum known flood.

5.6 OVERTOPPING POTENTIAL

Analysis using the PMF and one-half the PMF indicates that the dam does not have sufficient spillway capacity. The inflow from the PMF is 2632 cfs and for one-half the PMF the inflow is 1316 cfs. For a PMF peak outflow of 2582 cfs, the dam would be overtopped to a computed depth of 4.4 feet. For the peak outflow of one-half the PMF, the depth of overtopping would be 2.6 feet. All storms exceeding 10% of the PMF will result in the dam being overtopped. The spillway in its present configuration only has sufficient capacity to discharge 135 cfs.

5.7 EVALUATION

Using the Corps of Engineers screening criteria for initial review of spillway adequacy, it has been determined that the dam would be overtopped by all storms exceeding 10% of the PMF. Since a failure of the dam would increase the hazard to the downstream residents over that which would exist just prior to the failure, the spillway capacity is adjudged to be seriously inadequate.

SECTION 6: STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observations

Visual observations revealed that the structure is in poor condition. There were two locations where substantial voids had developed in the structure. These voids were caused by the structure unravelling, probably due to overtopping. There were also indications of distress at the right abutment. The lines formed by the stones across the dam were no longer horizontal but were displaced upward. A slight outward bulge was noted in the lower portion of the structure near the center of the spillway section.

b. Data Review and Stability Evaluation

There were no plans available from which information needed to perform a stability analysis could be obtained. Due to this lack of information and due to the type of structure, a stability analysis was not considered feasible.

SECTION 7: ASSESSMENT/RECOMMENDATIONS

7.1 ASSESSMENT

a. Safety

The Phase I inspection of the Stump Pond Dam revealed the dam to be in poor condition with several serious deficiencies. The right spillway section has failed, creating a large void in this part of the dam. Another large void exists on the left end of the dam. There were several smaller voids and overall deterioration on the left spillway channel. The earth fill on the upstream face has resulted in severely limited spillway capacity. Engineering investigations indicate that the spillway capacity is seriously inadequate (unable to discharge the outflow of 1/2 the PMF). Due to the deficiencies which exist on this structure, the dam has been assessed as "unsafe."

b. Adequacy of Information

There was very little information available for the preparation of this report. Most of the information used was obtained from observations and measurements made at the time of the inspection.

c. Need for Additional Investigations

A number of the deficiencies on this structure were related to the stability of the dam. Due to insufficient data, no stability analysis was performed for this dam. An overall analysis of the stability of the structure is required to determine the cause of the bulge on the downstream face and if modifications to the dam are needed.

Since the spillway was assessed as seriously inadequate, additional hydrologic/hydraulic investigations are required to more accurately determine the site specific characteristics of the watershed. Remedial measures for increasing the spillway capacity are then required.

d. Urgency

Due to the poor condition of this structure, it should be given immediate attention. Within 30 days of the notification to the owner that the dam has been classified as unsafe, repair work on the structural deficiencies (voids on spillway and dam, cracked concrete, etc.), should be commenced. These repairs should be completed within 3 months.

The additional detailed hydrologic/hydraulic investigations should be commenced within 3 months of the date of notification of the owner. A stability analysis for the structure should be commenced within 6 months.

Mitigating measures deemed necessary as a result of the investigations and repairs required should be completed within 1 year of the date of notification.

7.2 RECOMMENDED MEASURES

- a. Repair large voids which exist on the right spillway channel and on the left end of the dam.

- b. Repair the left spillway channel, including cracked concrete and voids in the channel.
- c. Remove the pier between the two spillway channels.
- d. Remove the earth fill in front of spillway channels down to the level of the spillway crest.
- e. Provide additional spillway capacity as a result of detailed hydrologic/hydraulic investigations.
- f. Direct surface runoff away from right abutment slope on downstream face to prevent erosion of the slope.
- g. Cut trees along downstream toe of the dam.
- h. Make modifications to the structure deemed necessary as a result of the stability analysis.
- i. Repair cracked concrete abutments on either end of the spillway.
- j. Provide a reservoir drain to permit the controlled lowering of the impoundment.
- k. Develop an emergency action plan for the notification of downstream residents.

APPENDIX A

PHOTOGRAPHS




Photo 1 - Failed Right Spillway Section



Photo 2 - Close-up View of Failed Spillway Section



Photo 3 - Left Spillway Section; Note Separation Between
Concrete Wall and Spillway Slab



Photo 4 - Undermined Pier Between Spillway Sections




Photo 5 - Earth Fill Upstream of Dam



Photo 6 - Void on Downstream Face at Left End of Dam



Photo 7 - Downstream Face of Dam -- Note Slight Bulge in Middle and Trees Growing Along Toe



Photo 8 - Downstream Face of Dam -- Note Tilting Stones to Left and Concrete Footing at Base of Dam



Photo 9 - Downstream of Dam -- Trees Growing Along Toe



Photo 10 - Cracked Abutment at Left End of Spillway

APPENDIX B

VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST1) Basic Data

a. General

Name of Dam STUMP POND DAM
Fed. I.D. # 746 DEC Dam No. 95A-4270
River Basin SUSQUEHANNA
Location: Town WILLET County CORTLAND
Stream Name WILLET CREEK
Tributary of OTSELIC RIVER
Latitude (N) 42° 27.7' Longitude (W) 75° 53.5'
Type of Dam L.A.D UP STONE & EARTH FILL
Hazard Category C
Date(s) of Inspection 10/23/80
Weather Conditions 40° SUNNY CLEAR
Reservoir Level at Time of Inspection 4" ABOVE SPILL CREST
b. Inspection Personnel W. C. LYNICK ; R. L. WARRENDER
c. Persons Contacted (Including Address & Phone No.) _____

d. History:
Date Constructed ? Date(s) Reconstructed _____
Designer UNKNOWN
Constructed By UNKNOWN
Owner WILLIAM SUDBRINK P.O. Box 42, WILLET, N.Y.

2) Embankment

a. Characteristics

- (1) Embankment Material TILL TYPE MATERIAL
- (2) Cutoff Type NONE
- (3) Impervious Core NONE
- (4) Internal Drainage System NONE
- (5) Miscellaneous EARTH FILL APPEARS TO HAVE BEEN PLACED AFTER CONSTRUCTION OF DAM EITHER TO CUT SEEPAGE OR FORM ROAD

b. Crest

- (1) Vertical Alignment VERY IRREGULAR - RESULT OF OVERTOPPING. 2 LOW SPOTS - ONE IN FRONT OF FAILED SECTION - THE OTHER IS OPEN CHANNEL WHICH NOW ACTS AS SPILLWAY - ABOUT 10' WIDE & 2' DEEP.
- (2) Horizontal Alignment OKAY

- (3) Surface Cracks SOME IN ERODED AREAS OF OVERTOPPING (ACTING TO WIDEN OPEN CHANNEL)
- (4) Miscellaneous WATER FLOWS THROUGH LOW AREA & OVER SOME TYPE OF LIP WHICH IS SEPARATED FROM MAIN SPILLWAY SECTION & PLUNGES INTO DAM - NOT OVER SPILLWAY

c. Upstream Slope

- (1) Slope (Estimate) (V:H) FLAT
- (2) Undesirable Growth or Debris, Animal Burrows SOME BRUSH
- (3) Sloughing, Subsidence or Depressions DEPRESSIONS RELATING TO CREST DEPRESSIONS

(4) Slope Protection SOME STONE ON SLOPE BUT GENERALLY UNPROTECTED

(5) Surface Cracks or Movement at Toe _____

d. Downstream Slope

(1) Slope (Estimate - V:H) ESTIMATED VERTICAL - UP AGAINST MASONRY

(2) Undesirable Growth or Debris, Animal Burrows ^{DAM} N/A

(3) Sloughing, Subsidence or Depressions N/A

(4) Surface Cracks or Movement at Toe N/A

(5) Seepage N/A

(6) External Drainage System (Ditches, Trenches; Blanket) _____

N/A

(7) Condition Around Outlet Structure N/A

(8) Seepage Beyond Toe N/A

e. Abutments - Embankment Contact

STEEP ABUTMENTS - CONTACT APPEARS TO BE SATISFACTORY

93-15-3(9/80)

- (1) Erosion at Contact SOME EROSION FROM RUN OFF AT DOWNSTREAM
CONTACT - STEEP ABUTMENT AT D.S. RIGHT ABUTMENT
HAS POTENTIAL TO BE AN EROSION PROBLEM
- (2) Seepage Along Contact _____

3) Drainage System

a. Description of System NONE

b. Condition of System _____

c. Discharge from Drainage System _____

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs, Piezometers, Etc.) _____

NONE

5) Reservoir

- a. Slopes FLAT
- b. Sedimentation APPEARS TO BE CONSIDERABLE SILTATION NEAR THE DAM
- c. Unusual Conditions Which Affect Dam STUMPS STICKING UP THRU LAKE SEEM TO INDICATE THAT LAKE IS SHALLOW

6) Area Downstream of Dam

- a. Downstream Hazard (No. of Homes, Highways, etc.) HAMLET OF GEORGETOWN
3 HOUSES 1 TRAILER - VILLAGE OF WILLET
- b. Seepage, Unusual Growth NONE
- c. Evidence of Movement Beyond Toe of Dam NONE
- d. Condition of Downstream Channel TREES IN FAIRLY NARROW CHANNEL

7) Spillway(s) (Including Discharge Conveyance Channel)

2 CHANNELS - ONE OF WHICH HAS FAILED - EARTH FILL HAD BEEN PLACED UPSTREAM OF BOTH BUT IT IS NOW OPEN IN FRONT OF LEFT SPILLWAY

- a. General PIER WHICH SEPARATES THE LEFT & RIGHT CHANNELS IS CRACKED & ALMOST COMPLETELY UNDERMINED.
- b. Condition of ~~Spillway~~ ^{LEFT} Spillway CONCRETE OVER STONE, WATER NOW FLOWING OVER 2' WIDE CONCRETE LIP & DRIPPING INTO LAID UP STONE. 2 VOIDS IN THIS SECTION ONE NEAR CENTER OF SECTION, THE OTHER AT RIGHT END. STONES AT DOWNSTREAM FACE OVERHANG THE LAID UP STONE DAM.

c. Condition of ^{RIGHT} ~~Auxiliary~~ Spillway - LOOKS LIKE IT WAS ORIGINALLY THE
SAME AS LEFT ONE - NOW IT HAS FAILED. SEMICIRCULAR
VOID ABOUT 3' DEEP & 3' WIDE - STONES OF DAM HAVE
JUST PEELED OFF - SEE PHOTOS - EARTH FILL PREVENTS
WATER FROM FLOWING IN THIS CHANNEL

d. Condition of Discharge Conveyance Channel _____

STONE FILLED - TREE LINED

8) Reservoir Drain/Outlet

NO DRAIN APPARENT - A 1' SQUARE OPENING WAS
NOTED ON DOWNSTREAM FACE BUT IT ONLY EXTENDED
A FEW FEET INTO THE DAM - ROOTS FROM ADJACENT
TREES WERE GROWING THROUGH DAM & INTO THIS
OPENING.

9) Structural

- a. Concrete Surfaces CRACKED DETERIORATED; VOIDS ON CONCRETE
ON LEFT SPILLWAY CHANNEL
- b. Structural Cracking YES - PIER & ABUTMENTS OF SPILLWAY
HAVE CRACKING - CRACKS ON SPILLWAY SECTION AS WELL
- c. Movement - Horizontal & Vertical Alignment (Settlement) ONE SLIGHT
BULGE IN CENTER OF STRUCTURE - BELOW SPILLWAY SECTION.
STONE SOMEWHAT TIPPING ON BOTH ENDS OF DAM - WORST
~~at~~ Junctions with Abutments to Abutments ON RIGHT HAND END
STONE IN CENTER IS PRETTY STRAIGHT
- e. Drains - Foundation, Joint, Face NONE
- f. Water Passages, Conduits, Sluices SEE SPILLWAY DESCRIPTION
- g. Seepage or Leakage NONE NOTED - MASONRY SEEMS TO REST
ON CONCRETE BASE - ONE VERTICAL CRACK IN BASE AT
ABOUT CENTER OF DAM - SOME OF WATER DISAPPEARING
INTO DAM SEEMS TO COME THROUGH HERE. UPON INCREASING
FLOW OVER SPILLWAY FLOW UNDER & THROUGH DAM SEEMED
TO SPREAD ACROSS WIDER AREA.

- h. Joints - Construction, etc. NONE
- i. Foundation CONCRETE - NO BEDROCK APPARENT AT DAM OR IN CHANNEL
- j. Abutments VERY STEEP RIGHT ABUTMENT - SOME SURFACE EROSION
- k. Control Gates NONE
- l. Approach & Outlet Channels
- m. Energy Dissipators (Plunge Pool, etc.) NONE
- n. Intake Structures NONE
- o. Stability QUESTIONABLE - AT ENDS IT ALMOST APPEARS THAT TREES ARE BUTRESSING DAMS - TREE ROOTS DO GO INTO DAM
- p. Miscellaneous VOID AT LEFT END OF LEFT SPILLWAY ABOUT 5' DEEP FROM CREST & 2' WIDE - COMPLETE REMOVAL OF STONES IN THIS AREA - REMAINING DAM ONLY ABOUT 18" WIDE AT CREST. CAUSE OF THIS VOID IS UN CLEAR

APPENDIX C

HYDROLOGIC/HYDRAULIC
ENGINEERING DATA AND COMPUTATIONS

CHECK LIST FOR DAMS
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

1

AREA-CAPACITY DATA:

	<u>Elevation</u> (ft.)	<u>Surface Area</u> (acres)	<u>Storage Capacity</u> (acre-ft.)
1) Top of Dam	<u>1265</u>	<u>59</u>	<u>260</u>
2) Design High Water (Max. Design Pool)	<u> </u>	<u> </u>	<u> </u>
3) Auxiliary Spillway Crest	<u>1262</u>	<u>39</u>	<u>200</u>
4) Pool Level with Flashboards	<u> </u>	<u> </u>	<u> </u>
5) Service Spillway Crest	<u> </u>	<u> </u>	<u> </u>

DISCHARGES

	<u>Volume</u> (cfs)
1) Average Daily	<u> </u>
2) Spillway @ Maximum High Water	<u>135</u>
3) Spillway @ Design High Water	<u> </u>
4) Spillway @ Auxiliary Spillway Crest Elevation	<u> </u>
5) Low Level Outlet	<u> </u>
6) Total (of all facilities) @ Maximum High Water	<u> </u>
7) Maximum Known Flood	<u> </u>
8) At Time of Inspection	<u>0</u>

CREST:

ELEVATION: 1265Type: EARTH & LAID UP STONEWidth: 8.5' Length: 100'Spillover 2-CHANNELS 1-FAILED & BLOCKED- 1-PARTIALLY BLOCKEDLocation CENTER OF DAM

SPILLWAY:

SERVICE

AUXILIARY

1262

Elevation

CONCRETE CREST

Type

15.0' - (10' EFFECTIVE)

Width

Type of Control

✓

Uncontrolled

Controlled:

Type

(Flashboards; gate)

Number

Size/Length

Invert Material

Anticipated Length
of operating service

Chute Length

Height Between Spillway Crest
& Approach Channel Invert
(Weir Flow)

HYDROMETEROLOGICAL GAGES:

Type : NONE

Location: _____

Records:

Date - _____

Max. Reading - _____

FLOOD WATER CONTROL SYSTEM:

Warning System: NONE

Method of Controlled Releases (mechanisms):

NONE

DRAINAGE AREA: 870 ACRES

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: FARM FIELDS & WOOD LANDS

Terrain - Relief: MODERATE TO STEEP

Surface - Soil: SOMEWHAT ROCKY

Runoff Potential (existing or planned extensive alterations to existing
(surface or subsurface conditions)

NONE

Potential Sedimentation problem areas (natural or man-made; present or future)

APPEARS TO BE SUBSTANTIAL SEDIMENTATION

Potential Backwater problem areas for levels at maximum storage capacity
including surcharge storage:

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the
Reservoir perimeter:

Location: _____

Elevation: _____

Reservoir:

Length @ Maximum Pool _____ (Miles)

Length of Shoreline (@ Spillway Crest) _____ (Miles)

PROJECT GRID

JOB	STUMP POND DAM		SHEET NO.	1	CHECKED BY		DATE	
SUBJECT	HYDROLOGIC / HYDRAULIC COMPUTATIONS				COMPUTED BY	RLW	DATE	10/27/80
DRAINAGE AREA - PLANIMETERED								
			8.40 IN ²	WILLET QUAD				
			1.07 IN ²	SMITHVILLE FLATS QUAD				
			9.47 IN ² = 869.6 ACRES = 1.36 SQ MI					
SURFACE AREA - PLANIMETERED								
			ELEVATION 1262 - .42 IN ² = 38.6 ACRES					
SNYDER SYNTHETIC UNIT HYDROGRAPH								
L = 1.74 MI			L _{CA} = .87 MI					
PMP = 20.5			C ₁ → USE 2.0					
$t_p = C_1 (L + L_{CA})^2 = 2.0 [(1.74 + .87)]^2 = 2.26 \text{ HOURS}$								
$t_r = \frac{t_p}{5.5} = \frac{2.26}{5.5} = .41 \quad \text{USE 15 minute hydrograph}$								
$t_{pr} = t_p + .25(t_r - t_p) = 2.26 + .25(.25 - .41) = 2.22$								
$TRSPC = T.E. = 1 - \frac{.3008}{(1.86)^{.7778}} = .717$								
RAILWAY CAPACITY - CHANNEL IN EARTH FILL								
$L = 10'$								
$Q = CL H^{3/2} = (2.6)(10)(3)^{1.5} = 135 \text{ cfs}$								

 NEW YORK STATE
 DEPT OF ENVIRONMENTAL CONSERVATION
 FLOOD PROTECTION BUREAU

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 26 FEB 79
 MODIFIED FOR MONEYPHILL APR 79

1 A1 STUMP POND DAM
 2 A2 PMF WITH RATIOS
 3 A3 OVERTOPPING ANALYSIS
 4 B 15C 0 15
 5 B1 5
 6 J 1 3 1
 7 J1 .1 .5 1.0
 8 K C 1
 9 K1
 10 H 1 1 1.36
 11 P C 20.5 111 123 132 142
 12 T
 13 W 2.22 .625
 14 X 2 2 1
 15 K 1 1
 16 K1
 17 Y 1 1
 18 Y1 1
 19 Y4 1262 1263 1264 1264.5 1265
 20 Y5 C 26 73 103 135
 21 \$5 20C 260
 22 \$E 1262 1265
 23 \$5 1262
 24 \$D 1265 2.6 1.5 90
 25 K 99
 26 A
 27 A
 28 A
 29 A
 30 A

INFLOW HYDROGRAPH

.717
 1

1 .1

-1262 -1

ROUTED HYDROGRAPH

 FLOOD HYDROGRAPH PACKAGE (HFC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 26 FEB 79
 MODIFIED FOR HONEYWELL APR 79

RUN DATE 02/11/81

STLMP POND DAM
 PWF WITH RATICS
 CVERTOPPING ANALYSIS

NC NHR NMN IDAY IHR IMN METRC IPLY IPRT NSTAN
 15C 0 15 0 0 0 2 0 0
 JOPER 5 LROPT TRACE
 0 0 0

JOB SPECIFICATION

MULTI-PLAN ANALYSES TO BE PERFORMED
 NPLAN= 1 NRYID= 3 LATID= 1

RTICS= 0.10 0.50 1.00

SUB-AREA RUNOFF COMPUTATION

INFLOW HYDROGRAPH
 ISTAQ ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO
 1 0 0 0 0 0 1 0 0

HYDROGRAPH DATA
 INYDC IUNG TAREA SNAP TRSDA TRSPC RATIO ISNCH ISAME LOCAL
 1 1 1.36 0. 1.36 0.72 0. 0 1 0

PRECIP DATA
 SPFE PMS R6 R12 R24 R48 R72 R96
 0. 20.50 111.00 123.00 132.00 142.00 0. 0.

LOSS DATA
 LROPT STRKR DLTKR RTIOL ERAIN STRKS RTIOK STRTL CNSTL ALSMX RTIMP
 0 C. 0. 1.00 0. 0. 1.00 1.00 0.10 0. 0.

UNIT HYDROGRAPH DATA
 TP= 2.22 CP=0.63 NTA= C

APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 9.90 AND R= 8.23 INTERVALS

UNIT HYDROGRAPH 49 END-OF-PERIOD ORDINATES, LAG= 2.22 HOURS, CP= 0.63 VOL= 1.00
 9. 34. 68. 107. 150. 190. 222. 243. 252. 247.
 227. 201. 178. 158. 140. 124. 110. 97. 86. 76.
 67. 53. 47. 42. 37. 33. 29. 26. 23. 23.
 20. 18. 14. 12. 11. 10. 9. 8. 7. 7.
 6. 5. 4. 4. 3. 3. 3. 2. 2. 2.

END-OF-PERIOD FLOW
 MO.DA HR.MN PERICO RAIN EXCS LOSS COMP Q HQ.DA PR.MN PERICO RAIN EXCS LCSS COMP C
 1.01 0.15 1 0.00 0. 0.00 2. 1.02 0.15 97 0.02 0. 0.02 5.
 1.01 0.30 2 0.00 0. 0.00 2. 1.02 0.30 98 0.02 0. 0.02 5.
 1.01 0.45 3 0.00 0. 0.00 2. 1.02 0.30 98 0.02 0. 0.02 5.

 NEW YORK STATE
 DEPT OF ENVIRONMENTAL CONSERVATION
 FLOOD PROTECTION BUREAU

1.01	1.00	0.00	2.	1.02	1.00	100	0.02	0.	0.02	4.
1.01	1.15	0.00	2.	1.02	1.15	101	0.02	0.	0.02	4.
1.01	1.30	0.00	2.	1.02	1.30	102	0.02	0.	0.02	4.
1.01	1.45	0.00	2.	1.02	1.45	103	0.02	0.	0.02	4.
1.01	2.00	0.00	2.	1.02	2.00	104	0.02	0.	0.02	3.
1.01	2.15	0.00	2.	1.02	2.15	105	0.02	0.	0.02	3.
1.01	2.30	0.00	2.	1.02	2.30	106	0.02	0.	0.02	3.
1.01	2.45	0.00	2.	1.02	2.45	107	0.02	0.	0.02	3.
1.01	3.00	0.00	2.	1.02	3.00	108	0.02	0.	0.02	3.
1.01	3.15	0.00	2.	1.02	3.15	109	0.02	0.	0.02	3.
1.01	3.30	0.00	2.	1.02	3.30	110	0.02	0.	0.02	3.
1.01	3.45	0.00	2.	1.02	3.45	111	0.02	0.	0.02	3.
1.01	4.00	0.00	2.	1.02	4.00	112	0.02	0.	0.02	2.
1.01	4.15	0.00	2.	1.02	4.15	113	0.02	0.	0.02	2.
1.01	4.30	0.00	2.	1.02	4.30	114	0.02	0.	0.02	2.
1.01	4.45	0.00	2.	1.02	4.45	115	0.02	0.	0.02	2.
1.01	5.00	0.00	2.	1.02	5.00	116	0.02	0.	0.02	2.
1.01	5.15	0.00	2.	1.02	5.15	117	0.02	0.	0.02	2.
1.01	5.30	0.00	2.	1.02	5.30	118	0.02	0.	0.02	2.
1.01	5.45	0.00	2.	1.02	5.45	119	0.02	0.	0.02	2.
1.01	6.00	0.00	2.	1.02	6.00	120	0.02	0.	0.02	2.
1.01	6.15	0.01	2.	1.02	6.15	121	0.07	0.05	0.03	2.
1.01	6.30	0.01	2.	1.02	6.30	122	0.07	0.05	0.03	4.
1.01	6.45	0.01	2.	1.02	6.45	123	0.07	0.05	0.03	7.
1.01	7.00	0.01	2.	1.02	7.00	124	0.07	0.05	0.03	13.
1.01	7.15	0.01	2.	1.02	7.15	125	0.07	0.05	0.03	20.
1.01	7.30	0.01	2.	1.02	7.30	126	0.07	0.05	0.03	29.
1.01	7.45	0.01	2.	1.02	7.45	127	0.07	0.05	0.03	40.
1.01	8.00	0.01	2.	1.02	8.00	128	0.07	0.05	0.03	52.
1.01	8.15	0.01	2.	1.02	8.15	129	0.07	0.05	0.03	64.
1.01	8.30	0.01	2.	1.02	8.30	130	0.07	0.05	0.03	76.
1.01	8.45	0.01	2.	1.02	8.45	131	0.07	0.05	0.03	87.
1.01	9.00	0.01	2.	1.02	9.00	132	0.07	0.05	0.03	97.
1.01	9.15	0.01	2.	1.02	9.15	133	0.07	0.05	0.03	109.
1.01	9.30	0.01	2.	1.02	9.30	134	0.07	0.05	0.03	113.
1.01	9.45	0.01	2.	1.02	9.45	135	0.07	0.05	0.03	120.
1.01	10.00	0.01	2.	1.02	10.00	136	0.07	0.05	0.03	126.
1.01	10.15	0.01	2.	1.02	10.15	137	0.07	0.05	0.03	131.
1.01	10.30	0.01	2.	1.02	10.30	138	0.07	0.05	0.03	136.
1.01	10.45	0.01	2.	1.02	10.45	139	0.07	0.05	0.03	140.
1.01	11.00	0.01	2.	1.02	11.00	140	0.07	0.05	0.03	144.
1.01	11.15	0.01	2.	1.02	11.15	141	0.07	0.05	0.03	147.
1.01	11.30	0.01	2.	1.02	11.30	142	0.07	0.05	0.03	150.
1.01	11.45	0.01	2.	1.02	11.45	143	0.07	0.05	0.03	152.
1.01	12.00	0.01	2.	1.02	12.00	144	0.07	0.05	0.03	155.
1.01	12.15	0.03	2.	1.02	12.15	145	0.41	0.38	0.02	160.
1.01	12.30	0.03	2.	1.02	12.30	146	0.41	0.38	0.02	173.
1.01	12.45	0.03	2.	1.02	12.45	147	0.41	0.38	0.02	197.
1.01	13.00	0.03	2.	1.02	13.00	148	0.41	0.38	0.02	234.
1.01	13.15	0.04	2.	1.02	13.15	149	0.49	0.46	0.02	286.
1.01	13.30	0.04	2.	1.02	13.30	150	0.49	0.46	0.02	354.
1.01	13.45	0.04	2.	0.	0.	151	0.49	0.46	0.02	435.
1.01	14.00	0.04	2.	0.	0.	152	0.49	0.46	0.02	525.
1.01	14.15	0.05	2.	0.	0.	153	0.61	0.59	0.02	624.
1.01	14.30	0.05	2.	0.	0.	154	0.61	0.59	0.02	727.
1.01	14.45	0.05	2.	0.	0.	155	0.61	0.59	0.02	830.
1.01	15.00	0.05	2.	0.	0.	156	0.61	0.59	0.02	931.
1.01	15.15	0.05	2.	0.	0.	157	0.62	0.59	0.02	1030.
1.01	15.30	0.09	2.	0.	0.	158	1.24	1.21	0.03	1132.
1.01	15.45	0.23	2.	0.	0.	159	3.47	3.45	0.03	1267.
1.01	16.00	0.04	3.	0.	0.	160	0.87	0.84	0.02	1449.
1.01	16.15	0.03	6.	0.	0.	161	0.57	0.55	0.02	1661.
1.01	16.30	0.03	9.	0.	0.	162	0.57	0.55	0.02	1883.
1.01	16.45	0.03	13.	0.	0.	163	0.57	0.55	0.02	2105.
1.01	17.00	0.03	18.	0.	0.	164	0.57	0.55	0.02	2308.

1.01	17.30	70	0.03	0.01	0.03	29.	0.	0.	100	0.45	0.42	0.03	2632.
1.01	17.45	71	0.03	0.01	0.03	33.	0.	0.	167	0.45	0.42	0.03	2632.
1.01	18.00	72	0.03	0.01	0.03	37.	0.	0.	168	0.45	0.42	0.03	2632.
1.01	18.15	73	0.00	0.	0.00	39.	0.	0.	169	0.03	0.01	0.03	2645.
1.01	18.30	74	0.00	0.	0.00	40.	0.	0.	170	0.03	0.01	0.03	2645.
1.01	18.45	75	0.00	0.	0.00	40.	0.	0.	171	0.03	0.01	0.03	2645.
1.01	19.00	76	0.00	0.	0.00	38.	0.	0.	172	0.03	0.01	0.03	2645.
1.01	19.15	77	0.00	0.	0.00	37.	0.	0.	173	0.03	0.01	0.03	2645.
1.01	19.30	78	0.00	0.	0.00	34.	0.	0.	174	0.03	0.01	0.03	2645.
1.01	19.45	79	0.00	0.	0.00	32.	0.	0.	175	0.03	0.01	0.03	2645.
1.01	20.00	80	0.00	0.	0.00	29.	0.	0.	176	0.03	0.01	0.03	2645.
1.01	20.15	81	0.00	0.	0.00	26.	0.	0.	177	0.03	0.01	0.03	2645.
1.01	20.30	82	0.00	0.	0.00	23.	0.	0.	178	0.03	0.01	0.03	2645.
1.01	20.45	83	0.00	0.	0.00	21.	0.	0.	179	0.03	0.01	0.03	2645.
1.01	21.00	84	0.00	0.	0.00	19.	0.	0.	180	0.03	0.01	0.03	2645.
1.01	21.15	85	0.00	0.	0.00	17.	0.	0.	181	0.03	0.01	0.03	2645.
1.01	21.30	86	0.00	0.	0.00	15.	0.	0.	182	0.03	0.01	0.03	2645.
1.01	21.45	87	0.00	0.	0.00	14.	0.	0.	183	0.03	0.01	0.03	2645.
1.01	22.00	88	0.00	0.	0.00	12.	0.	0.	184	0.03	0.01	0.03	2645.
1.01	22.15	89	0.00	0.	0.00	11.	0.	0.	185	0.03	0.01	0.03	2645.
1.01	22.30	90	0.00	0.	0.00	10.	0.	0.	186	0.03	0.01	0.03	2645.
1.01	22.45	91	0.00	0.	0.00	9.	0.	0.	187	0.03	0.01	0.03	2645.
1.01	23.00	92	0.00	0.	0.00	8.	0.	0.	188	0.03	0.01	0.03	2645.
1.01	23.15	93	0.00	0.	0.00	8.	0.	0.	189	0.03	0.01	0.03	2645.
1.01	23.30	94	0.00	0.	0.00	7.	0.	0.	190	0.03	0.01	0.03	2645.
1.01	23.45	95	0.00	0.	0.00	6.	0.	0.	191	0.03	0.01	0.03	2645.
1.02	0.	96	0.00	0.	0.00	6.	0.	0.	192	0.03	0.01	0.03	2645.

SUM 20.87 17.25 3.62 5845.
 (530.11 438.11 92.11 1666.36)

CFS	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VECTME
CHS	2632.	1850.	603.	306.	58718.	
INCHES	75.	52.	17.	5.	1663.	
MM		12.65	16.51	16.73	16.73	
AC-FT		321.43	419.31	425.06	425.06	
TOTALS CU M		917.	1197.	1213.	1213.	
		1132.	1476.	1496.	1496.	

11:FLOW(I), OUTFLOW(O) AND OBSERVED FLOW(*)

[illegible]

[illegible]

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	263.	185.	60.	31.	5872.
CMS	7.	5.	2.	1.	166.
INCHES		1.27	1.65	1.67	
MM		32.14	41.93	42.51	
AC-FT		92.	120.	121.	
TDOLS CU M		113.	148.	150.	

[illegible]

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1316.	925.	302.	153.	29359.
CMS	37.	26.	9.	4.	831.
INCHES		6.33	8.25	8.37	8.37
MM		160.72	209.65	212.53	212.53
AC-FT		459.	598.	607.	607.
TDLS CU M		566.	738.	748.	748.

PEAK OUTFLOW IS 147. AT TIME 44.00 HOURS

PEAK	0-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
147.	122.	38.	19.	3685.	
4.	3.	1.	1.	104.	
	0.84	1.04	1.05	1.05	
	21.28	26.42	26.67	26.67	
	61.	75.	76.	76.	
	75.	93.	94.	94.	

CFS
CNS
INCHES
MM
AC-FY
T-DLS CU M

STATION 1

INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(*)

[illegible]

7.3012001
7.4512701
8.0012801
8.1512901
8.3013001
8.4513101
9.0013201
9.1513301
9.3013401
9.4513501
10.0013601
10.1513701
10.3013801
10.4513901
11.0014001
11.1514101
11.3014201
11.4514301
12.0014401
12.1514501
12.3014601
12.4514701
13.0014801
13.1514901
13.3015001
13.4515101
13.6015201
13.7515301
13.9015401
14.0515501
14.2015601
14.3515701
14.5015801
14.6515901
14.8016001
14.9516101
15.1016201
15.2516301
15.4016401
15.5516501
15.7016601
15.8516701
16.0016801
16.1516901
16.3017001
16.4517101
16.6017201
16.7517301
16.9017401
17.0517501
17.2017601
17.3517701
17.5017801
17.6517901
17.8018001
17.9518101
18.1018201
18.2518301
18.4018401
18.5518501
18.7018601
18.8518701
19.0018801
19.1518901
19.3019001

STATION 1, PLAN 1, RATIC 2

END-OF-PERIOD HYDROGRAPH COORDINATES

[illegible][illegible][illegible]

7.4512701
8.0012801
8.151290
8.301300
8.451310
9.001320
9.151330
9.301340
9.451350
9.601360
9.751370
9.901380
9.951390
1.001400
1.151410
1.301420
1.451430
2.001440
2.151450
2.301460
2.451470
3.001480
3.151490
3.301500
0.151
0.152
0.153
0.154
0.155
0.156
0.157
0.158
0.159
0.160
0.161
0.162
0.163
0.164
0.165
0.166
0.167
0.168
0.169
0.170
0.171
0.172
0.173
0.174
0.175
0.176
0.177
0.178
0.179
0.180
0.181
0.182
0.183
0.184
0.185
0.186
0.187
0.188
0.189
0.190

[illegible][illegible][illegible]


1262.0	1264.0	1265.7	1266.8	1267.9	1268.0	1268.3	1268.4	1268.5	1268.6	1268.7	1268.8	1268.9	1269.0	1269.1	1269.2	1269.3	1269.4	1269.5	1269.6	1269.7	1269.8	1269.9
1263.5	1263.6	1263.7	1263.8	1263.9	1264.0	1264.1	1264.2	1264.3	1264.4	1264.5	1264.6	1264.7	1264.8	1264.9	1265.0	1265.1	1265.2	1265.3	1265.4	1265.5	1265.6	1265.7
1264.9	1265.3	1265.6	1265.9	1266.3	1266.5	1266.8	1266.9	1267.0	1267.1	1267.2	1267.3	1267.4	1267.5	1267.6	1267.7	1267.8	1267.9	1268.0	1268.1	1268.2	1268.3	1268.4
1267.7	1268.0	1268.4	1268.7	1269.0	1269.2	1269.3	1269.4	1269.5	1269.6	1269.7	1269.8	1269.9	1270.0	1270.1	1270.2	1270.3	1270.4	1270.5	1270.6	1270.7	1270.8	1270.9
1269.2	1269.1	1268.9	1268.7	1268.5	1268.3	1268.1	1267.9	1267.7	1267.5	1267.3	1267.1	1266.9	1266.7	1266.5	1266.3	1266.1	1265.9	1265.7	1265.5	1265.3	1265.1	1264.9
1267.2	1267.0	1266.9	1266.7	1266.5	1266.4	1266.3	1266.2	1266.1	1266.0	1265.9	1265.8	1265.7	1265.6	1265.5	1265.4	1265.3	1265.2	1265.1	1265.0	1264.9	1264.8	1264.7
1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8	1265.8

PEAK OUTFLOW IS 2582. AT TIME 42.25 HOURS

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
2582.	1835.	570.	287.	5592.	
73.	52.	16.	8.	1560.	
	12.55	15.60	15.70	15.70	
	318.86	396.25	398.81	398.81	
	910.	1131.	1138.	1138.	
	1123.	1395.	1404.	1404.	

TOTALS CU M

7.001251
7.131251
7.3012601
7.4312701
8.0012801
8.1312901
8.3013001
8.4313101
9.0013201
9.1313301
9.3013401
9.4313501
10.0013601
10.1313701
10.3013801
10.4313901
11.0014001
11.1314101
11.3014201
11.4314301
12.0014401
12.1314501
12.3014601
12.4314701
13.0014801
13.1314901
13.3015001
0.151.0
0.152.0
0.153.0
0.154.0
0.155.0
0.156.0
0.157.0
0.158.0
0.159.0
0.160.0
0.161.0
0.162.0
0.163.0
0.164.0
0.165.0
0.166.0
0.167.0
0.168.0
0.169.0
0.170.0
0.171.0
0.172.0
0.173.0
0.174.0
0.175.0
0.176.0
0.177.0
0.178.0
0.179.0
0.180.0
0.181.0
0.182.0
0.183.0
0.184.0
0.185.0
0.186.0
0.187.0
0.188.0



PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FORMULTE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS		
				RATIO 1	RATIO 2	RATIO 3
				0.10	0.50	1.00
HYDROGRAPH AT	1	1.36	1	263.	1316.	2632.
	(0.3CE 19)		(7.45)(37.26)(74.53)(
ROUTED TO	1	1.36	1	147.	1280.	2582.
	(0.3CE 19)		(4.17)(36.25)(73.12)(

APPENDIX D
REFERENCES

APPENDIX D

REFERENCES

- 1) U.S. Department of Commerce; Weather Bureau;
Hydrometeorological Report No. 33 - Seasonal Variation of the Probable
Maximum Precipitation East of the 105th Meridian for Areas from 10 to
1,000 Square Miles and Durations of 6, 12, 24, and 48 Hours, April 1956.
- 2) H.W. King and E.F. Brater, Handbook of Hydraulics, 5th edition,
McGraw-Hill, 1963.
- 3) University of the State of New York, Geology of New York, Education
Leaflet 20, Reprinted 1973.
- 4) Elwyn E. Seelye, Design, 3rd edition, John Wiley and Sons, Inc., 1960.
- 5) U.S. Department of the Interior, Bureau of Reclamations;
Design of Small Dams, 2nd edition (rev. reprint), 1977.


APPENDIX E
DRAWINGS

DAM SITE



VICINITY MAP
STUMP POND DAM
I.D. No. NY 746



DAM SITE



TOPOGRAPHIC MAP
STUMP POND DAM
I.D. No. NY 746

STUMP POND DAM SKETCH BASED ON FIELD MEASUREMENTS

SCALE 1"=10'



SECTION A-A

**DAT
FILM**